BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

SCHEDULE - B

Name of Work : .Restoration of Road cut portion done by BWSSB(For Water Line and sanitary Line) in Chikkasandra village Govt School surrounding area in Ward No.12, Shettyhalli Sub Division.

NAME OF AGENCY : PROFESSIONAL GLOBLAL INFRASTRUCTURE PVT LTD

Sl No	Description of items	Unit	Qty	Quoted Rate	Quoted Rate in words	Amount in Rupees
1	2	3	4	5	6	7
1	Restoration of road cut portion by removing and desposing all failed material, trimming of completed excavation to provide firm verticle faces, cleaning of surface, strenthening of subgrade, granualar sub base, wetmix macadam including premixing the material with water at OMC, Compaction and finaly applying prime cote, Tack code (900,1200 and 1500 MM width of road cutting,) and Asphalt layer of Bituminous macadam (900,1200 and 1500 MM width of road cutting,) and semidons bituminous concrete and restoration of rain cuts with specific soil as per the specification and drawing. Restoration of roads in Chikkasandra village Govt School.					
a	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (750mm width of road cutting)	Per mtr	350.00	785.33	Rupees Seven Hundred Eightyfive Paise Thirtythree Only	274865.50
b	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (900mm width of road cutting) for Water Line	Per mtr	3952.00	957.75	Rupees NineHundred Fiftyfive Paise seventyfive Only	3785028.00
c	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (1200mm width of road cutting) for sanitary Line	Per mtr	3840.00	1254.05	Rupees Onethousand Twohundred Fiftyfoure paise Five Only	4815552.00
	Grand Total					**8875445.50**

For Professional Global Infrastructure Pvt. Ltd.

Director

Contractor

Executive Engineer
Dasarahalli Division
BBMP, Bengaluru

Scanned by CamScanner